BRUHAT BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer, Dasarahalli Divisiion

SCHEDULE-B

Name of the Work: Providing pothole filling and other maintenance works at Ward no. 13, Mallasandra in Shettyhalli Sub-Division. (Emergency Grant)

Sl. No.	Description	Unit	Quantity.	Santioned Estimate Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift upto 0.5 m excavated surface leveled and sides neatly dressed the disposedd earth to be leveled nealty after breking of clods complete as per specification. Complete as per specification and direction of Engineer-in-charge of the work.	cum	50.47	196.56	Rupees One Hundred and Ninety Six and Fifty Six paisa Only
2	Providing laying, spreading and compacting graded stone aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with oaver in sub-base/base course on well prepared surface and compating with vibratory roller to achieve the desired density complete as per specifications. Complete as per specification and direction of Engineer-in-charge of the work.	cum	50.47	1801.44	Rupees One Thousand and Eight Hundred and One and Fourty Four Paisa Only
3	KSRRB 3000 Filling Pot-holes and Patch Repairs with Bituminous Concrete, 40 mm KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, filling back the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications MORTH Specification No. 3004.2. Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	252.36	307.80	Rupees Three Hundred and Seven and Eighty paisa Only
4	Earth work **for lowering and levelling the ground other than foundation works by mechanical means upto 3.00 depth**, including providing shoring and strutting, removal of stumps and other deleterious matter, dressing of sides and bottom, filling back the excavation earth to the extent required including the cost of labour & HOM of machineries, as per drawing and technical specification.	Cum	1704.43	181.44	Rupees One Hundred and Eighty One and Fourty Four paisa Only

Executive Engine
Dasarahalli Divic

Sig

Signature of the Contractor

Scanned by CamScanner

5	KSRB 2-1.2 : Earthwork in surface excavation in **Hard soil** for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1(a) / 2.3.1. (P.No. 5/I.No. 2.2 of CSR 2015-16)	Cum	730.47	237.60	Rupees Two and Thirty S Sixty pais
6	KSRB 2-1.2 : Earthwork in surface excavation in **Hard soil** for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1(a) / 2.3.1. (P.No. 5/I.No. 2.2 of CSR 2015-16)	Cum	87.30	167.40	Rupees One Hund and Sixty Seven a Fourty paisa Only
7	Dismantling size stone masonry in clay mortar and stacking the size stone within a radius of 50m and removing the debris to a distance upto 200m.	cum	61.38	185.76	Rupees One Hundred and Eighty Five and Seventy Six paisa Only
8	KSRB 4-1.2 : Providing and laying in position **plain cement concrete of mix 1:3:6** with OPC cement @ 220kgs. with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, **in foundation** including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No. 12/I.No. 4.2 of CSR 2015-16)	Cum	61.43	5449.68	Rupees Five Thousand and Four Hundred and Fourty Nine and Sixty Eight paisa Only
9	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13	Cum	38.34	2837.16	Rupees Two Thousand and Eight Hundred and Thirty Seven and Sixteen paisa Only
10	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13	Cum	245.70	5405.40	Rupees Five Thousand and Four Hundred and Five and Fourty paisa Only
11	KSRB 15.1.3 – do – Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	163.80	105.84	Rupees One Hundred and Five and Eighty Four paisa Only

Signature of the Contractor

Executive Enginee
Dasarahalli Dividic

Scanned by CamScanner

12	Providing and fixing for flooring 40mm thick sadarhalli grey flammed granite slab for bath areas in Bathrooms over a bed of 25mm thick CM 1:6 and fixing granite slab with CM 1:3.	Sqm	245.70	2042.28	Rupees Two Thousand and Fourty Two and Twenty Eight Paisa Only
13	Providing and laying in position plain cement concrete of mix 1:2:4 with OPC cement @ 40kgs, with 40mm and down size graded granite metal coarse aggregates @0.878 cum and fine aggregates @ 0.459 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all material, labour, HOM of machinery, cuting complete as per specifications Specification NO. KBS 4.1, 4.2 PWD 2016-17	Sqm	3.73	5630.04	Rupees Five Thousand and Six Hundred and Thirty Only

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Division, Bangalore-560057

Signature of the Contractor

Executive E
Dasarahalli

Scanned by CamScanner